Green Waste Management and Composting

De Almudena Urbieta

Green Waste Management and Composting. Collection: Biodiversity in the Factory Library. This technical guide analyzes the integration of biomass management in high-demand industrial and aeronautical environments, prioritizing risk mitigation and the optimization of ecosystem services.

Strategic Context. The in-situ management of plant remains is not an aesthetic choice, but a response to operational and legal risks. Compliance with current waste regulations requires absolute traceability. Internal biomass transformation reduces the logistical carbon footprint, contributes to decarbonization, and eliminates dependency on external waste managers, increasing resource efficiency and ensuring the continuity of ecosystem services within the factory perimeter.

Scientific and Technical Framework. The industrial composting process is based on the rigorous control of the Carbon/Nitrogen ratio and thermal phases. The thermophilic phase, where temperatures must be maintained between 55°C and 65°C, guarantees the sanitization of the material by eliminating pathogens and seeds of unwanted species. Constant monitoring of porosity and moisture is critical to ensure aerobic conditions, preventing methanogenesis and optimizing lignin degradation.

Field Analysis and Interferences. The coexistence between plant operations and biomass treatment zones requires precise zoning. Areas of influence where native biodiversity interacts with critical infrastructure must be identified. Field analysis must provide for leachate management and the stability of stockpiles against extreme weather events, ensuring that biomass management does not compromise structural integrity or facility accessibility.

Operational Safety: FOD Risk. In the aeronautical sector, biomass management must be compatible with operational safety. The risk of FOD (Foreign Object Debris) is critical. Protocols require that composting areas be located away from flight lines and hangars. Physical barriers and dispersion controls for volatile remains must be implemented to prevent organic matter from being ingested by turbines or blocking aircraft sensors, ensuring total interference mitigation.

Engineering Solutions and Protocols. Efficient management requires standardized protocols for reception, shredding, and turning. Process engineering defines intervention frequencies based on seasonally generated biomass volumes. The control of maintenance subcontractors must be governed by technical specifications that dictate the use of machinery free of hydraulic leaks and strict adherence to defined internal logistical routes.

Health and Safety (PPE). Personnel assigned to biomass handling must use full Personal Protective Equipment (PPE). This includes P3 filter respiratory protection to prevent the inhalation of bioaerosols and fungal spores during turning. Furthermore, the use of wrap-around eye protection, high-abrasion resistance gloves, and safety footwear with puncture-resistant soles is mandatory, following the most demanding occupational risk prevention standards.

Evaluation and Evidence of Success. Program success is measured through technical KPIs: percentage reduction of waste volume sent to landfills, tons of CO2 avoided by transport, and improvement in the site's native biodiversity index. Laboratory analysis of the final product must certify the absence of heavy metals and the stability of the organic material, transforming waste into a resource for soil restoration within the industrial complex itself.

Action Guide and Evaluation. Effective implementation concludes with a periodic internal audit. The checklist must include: verification of thermal parameters, PPE condition, absence of FOD in critical zones, and updating the biomass entry registry. Continuous evaluation allows protocols to be adjusted to seasonality, ensuring that decarbonization and environmental impact mitigation remain pillars of operational excellence.